SUMMARY OF THE BOQ

BOQ SUMMARY - KAMUNYOLO DAM REHABILITATION WORKS

ITEM	DESCRIPTION	AMOUNT (KES)
BILL No.1	PRELIMINARY AND GENERAL ITEMS	
BILL No.2	DAM EMBANKMENT	
BILL No.3	SPILLWAY	
BILL No.4	RIVER DIVERSION, DRAW OFF PIPE AND INTAKE TOWER	
SUB TOTA	L	
BILL No.5	DE-SILTING WORKS	
SUB TOTA	L	
Contingenci	es & price fluctuations (10 %)	
VAT (16 %)		
GRAND TO)TAL	

BOQ SUMMARY Page 1 of 6

BILL 1-PRELIMINARY AND GENERAL ITEMS

ITEM	DESCRIPTION	UNIT	QTY	RATE (KES)	AMOUNT (KES)
1.10	Provision of performance guarantee in accordance with instructions	Ls	1.0		
1.20	Provision of Insurance for the works	Ls	1.0		
1.30	Provision of insurance for workmen	Ls	1.0		
1.40	Mobilisation of machinery and equipment to site & Demobilization upon completion of the works	Ls	1.0		
1.50	Erection of contractors camp and office	Ls	1.0		
1.60	Setting out the works	Ls	1.0	150,000.00	150,000.00
1.70	Provision for testing of materials during construction	PS	1.0	100,000.00	100,000.00
1.80	Allow a sum of Ksh 1,500,000 for the attendance to the client's staff, allowance, transport	PS	1.0	1,500,000.00	1,500,000.00
1.90	Erect site office and maintain site office for the Engineer	months	6.0	45,000.00	270,000.00
1.10	Provide office equipment for the REs office	PS	1.0	100,000.00	100,000.00
1.11	Allow money for communication (telephone)	PS	1.0	30,000.00	30,000.00
II I	Rent house accomodation for Engineer and his staff (3No)	months	6.0		-
1.13	Allow for transport for the Engineer	months	6.0		-
1.14	Allow money for secretarial services	PS	1.0	250,000.00	250,000.00
II I	Provision for making and maintaining access roads	Ls	1.0		-
1.16	Additional Site Investigations	PS	1.0	100,000.00	100,000.00
1.17	Allow a Provisional sum of KES 200,000/-, to be spent in whole or part, for Environmental Conservation to be spent as directed by the Engineer	PS	1.0	200,000.00	200,000.00

Bill 1 P & G ITEMS Page 2 of 6

BILL 2 - EMBANKMENT

Item	Description	Unit	Quantity	Rate (KES)	Amount (KES)
	2.1 Care of water		•	, ,	
2/01	Care of water during construction in open air construction site	LS	1.00		
	2.2 Site Clearance				
2/02	Clearing and grubbing of dam embankment	m ²	10,000.00		
2/03	Clearing and grubbing of borrow area, spoil banks/areas and yards	m ²	10,000.00		
	2.3 Excavation				
2/04	Excavation, Common in open cut	m^3	8,500.00		
	2.4 Dam Embankment				
2/05	Compacted Earthfill for dam embankment	m ³	15,000.00		
2/06	Fine Filter -Sand	m ³	150.00		
2/07	Coarse Filter -Sand	m^3	125.00		
2/08	Rock Toe	m^3	750.00		
2/09	Riprap	m^3	540.00		
2/10	Gravel on dam crest	m^3	50.00		
2/11	Geo-textile	m ²	750.00		
	TOTAL CARRIED TO COLLECTION				_

Bill 2-Embankment Page 3 of 6

BILL 3 - SPILLWAY

ITEM	DESCRIPTION	UNIT	QTY	RATE (KES)	AMOUNT (KES)
	3.1 Care of water				
3/01	Care of water during construction in open air construction site	Ls	1.00		
	3.2 Earthworks				
3/02	Clearing and Grubbing, Bush	m ²	1,100.00		
3/03	Excavation, Common in open cut	m ³	1,050.00		
3/04	Excavation, Weathered Rock in open cut	m ³	100.00		
3/05	Excavation, Rock in open cut	m ³	100.00		
3/06	Backfilling, Random	m ³	620.00		
	3.3 Concrete works				
3/07	Boulder (Cyclopean) concrete	m ³	455.00		
3/08	Mass concrete Class C 15 (Weir and Subdam)	m ³	300.00		
3/09	Mass concrete Class C 15 (Retaining Walls)	m ³	480.00		
3/10	Form Work	m ²	950.00		
3/11	Reinforcement Bar	kg	2,000.00		
3/12	Elastic Filler, t=20mm	m ²	110.00		
	3.4 Metal Works				
3/13	Anchor Bar (Y20)	kg	40.00		
	3.5 Miscellaneous				
3/14	Weep Hole, Dia. 50mm	m	204.00		
	TOTAL CARRIED TO COLLECTION				<u>-</u>

Bill 3 - spillway Page 4 of 6

BILL 4 - RIVER DIVERSION, DRAW OFF PIPE AND INTAKE TOWER

ITEM	DESCRIPTION	UNIT	QTY	RATE (KES)	AMOUNT (KES)
	4.1 Care of water		Q	(====)	(22.20
4/01	Care of water during construction in open air construction site	Ls	1.00		
	4.2 Earthworks				
4/02	Site clearance	m ²	50.00		
4/04	Excavation, Common in open cut	m ³	500.00		
	4.3 Concrete works				
4/09	Concrete class C 25 (diversion culvert & intake tower)	m ³	15.00		
4/10	Mass concrete Class C 15	m ³	75.00		
4/12	Form Work	m ²	40.00		
4/14	Reinforcement Bar	kg	300.00		
	4.4 Pipe Work				
4/15	300 mm dia epoxy coated steel pipe and fittings	m	70.00		
4/16	150 mm dia epoxy coated steel pipe and fittings	m	83.00		
4/16	50 mm dia epoxy coated steel pipe and fittings	m	8.00		
	Total				
	Total				-

Bill 4 Draw off and intake Page 5 of 6

BILL 5 - DE-SILTING WORKS

Item	Description	Unit	Quantity	Rate (KES)	Amount (KES)
	5.1 Reservoir Desilting Works				
5/01	Clearing and grubbing of dam embankment	m ²	18,500.00		
5/02	Excavation and spoiling in deisgnted spoil banks or areas	m ³	37,000.00		
	TOTAL CARRIED TO COLLECTION				_

Bill 5 - De-silting Works Page 6 of 6